



**Our Ref:** QMFA 053/2014

**TITLE:** Limited period contract for the Commissioning, delivery and installation of Energy Efficient Soffit Cassettes Air Conditioners at the Ministry for Foreign Affairs

### **Clarification 3**

#### ***Question***

With regards to tender QMFA 053/2014 can you kindly clarify Index C and D from the BOQ please where you requested a price including all necessary chasing for PVC piping and a price including any necessary conduit, fittings etc.

#### ***Reply***

Kindly note that following consultation with the respective technical people, Item C is being altered as the chasing for either the laying of the drains or the electrical supply to the units is no longer required.

Item D is being removed from the BOQ. In the event of a commissioning (when this arises) prior to start of works, the supplier is to pay a site visit and identify if such works are necessary. If affirmative price related to the wiring including any necessary conduit, fittings etc., between the power supply and equipment will be given after site visit and this is to be taken as a variation to the contract. Only upon approval of the above the Ministry will issue the respective start of works.

Wednesday, 29<sup>th</sup> October, 2014

**Section B: Offer**

**SCHEDULE OF PRICE**

Item	Description	Qty	Unit	Rate	Amount
				as per clause S.07	as per clause S.07
	<p>To supply, deliver to site, install and connect up and commission the following equipment. All the items in this bill to conform to the accompanying specification.</p> <p><b>Cooling Capacities for the units shall be as specified or larger. Smaller sized units will not be accepted.</b></p>				
A	<p>Soffit Cassette type unit as specified. Cooling Capacity 5.0kW</p> <p>This is the minimum cooling capacity based on indoor temp. 27 deg.CDB, 19.5 deg. CWB and an outdoor temperature of 35 deg. CDB.</p>	2	no.		
B	<p>Twin refrigerant copper pipes (suct. &amp; disch.) complete with insulation etc. between the indoor and outdoor units extra to the 5m supplied with each unit</p>	20	m		
C	<p>PVC condensate drains from indoor units to discharge points as indicated, extra to the 5m supplied with each unit 20mm diameter</p>	20	m		
D	<p>Full maintenance for 60 months from commissioning.</p>	5	year		
				Grand Total Price	

Completion Period \_\_\_\_\_ days

Signature \_\_\_\_\_

Date \_\_\_\_\_

**Company Information:**

Full name of Company	
Address of Company	
Trading Licence No	
Valid up to	
Full name of contact person	
Contact Telephone Number / Mobile Number & Fax Number	
Email Address	
<b>VAT/ Registration number</b>	
Quotation Date	
Literature, Drawings, Digital Images and / or technical data of item being quoted	
A copy of the guarantee on all equipment for a period of 60 months as per Clause S.06	